

AD-A077 196

ARNOLD ENGINEERING DEVELOPMENT CENTER ARNOLD AFS TN  
WIND TUNNEL TEST TO INVESTIGATE AERODYNAMIC HYSTERESIS PHENOMEN--ETC(U)  
MAY 79 J F HERMAN  
AEDC-TSR-79-P27

F/G 1/3


UNCLASSIFIED

NL

| OF |  
AD-  
A077196



END  
DATE  
FILMED  
12-79  
DDC




AEDC-TSR-79-P27  
May 15, 1979

LEVEL  
*(2)*



WIND TUNNEL TEST  
TO INVESTIGATE AERODYNAMIC HYSTERESIS PHENOMENA  
OF THE F-4 AND F-111 AIRCRAFT MODELS

Joseph F. Herman  
ARO, Inc., AEDC Division  
A Sverdrup Corporation Company  
Propulsion Wind Tunnel Facility  
Arnold Air Force Station, Tennessee



AD A072196

Period Covered: March 27 - April 5, 1979

Approved for public release; distribution unlimited.

Reviewed By:

*Walter P. West*

WALTER P. WEST, Capt, USAF  
Test Director, PWT Division  
Directorate of Test Operations

Approved for Publication:

FOR THE COMMANDER

*James D. Sanders*

JAMES D. SANDERS, Colonel, USAF  
Director of Test Operations  
Deputy for Operations

Prepared For: AEDC Director of Test Engineering  
AEDC/DOTr  
Arnold AFS, Tennessee 37389

ARNOLD ENGINEERING DEVELOPMENT CENTER  
AIR FORCE SYSTEMS COMMAND  
ARNOLD AIR FORCE STATION, TENNESSEE

DDC FILE COPY

79 11 21 078

**UNCLASSIFIED**

## CONTENTS

	<u>Page</u>
NOMENCLATURE. . . . .	2
1.0 INTRODUCTION. . . . .	4
2.0 APPARATUS	
2.1 Test Facility. . . . .	5
2.2 Test Articles. . . . .	5
2.3 Instrumentation. . . . .	5
3.0 TEST DESCRIPTION	
3.1 Test Conditions and Procedures . . . . .	6
3.2 Corrections. . . . .	6
3.3 Data Reduction . . . . .	7
3.4 Uncertainty/Precision of Measurements. . . . .	7
4.0 DATA PACKAGE PRESENTATION . . . . .	7

## ILLUSTRATIONS

### Figure

1. Details and Dimensions of the F-4C Model. . . . .	8
2. Details and Dimensions of the F-111 Model . . . . .	13
3. Model Installation in Tunnel 4T . . . . .	15
4. Typical Flow-Visualization Results. . . . .	18

## TABLES

1. Tabulated Locations of Wing Static Pressure Orifices. . . . .	20
2. Model Configuration Nomenclature. . . . .	21
3. Summary of Nominal Test Conditions. . . . .	22
4. Data Uncertainties. . . . .	23
5. Test Program Part Number Summary. . . . .	25
6. Format for Tabulated Data . . . . .	28
7. Tabulated Data Nomenclature . . . . .	31

### NOMENCLATURE

A	Reference area; F-4, 1.325 ft <sup>2</sup> , F-111, 0.91146 ft <sup>2</sup>
AB	F-111 model base area, 0.03169 ft <sup>2</sup>
ALFA, $\alpha$	Model angle of attack measured between the relative wind vector and the reference waterline, deg
B	Wing span, F-4, 1.93 ft, F-111, 2.625 ft
BETA	Model sideslip angle, deg
BETA, $\beta_M$	Measured local wing surface flow angle in the yaw plane (Preston tube), deg
BL	Model buttline, in.
c	Local wing chord, in.
$\bar{c}$	Wing mean aerodynamic chord; F-4, 0.802 ft, F-111, 0.377 ft
C <sub>L</sub>	Model centerline
CA	Total axial-force coefficient, total axial force/Q.A
CAB	Base axial-force coefficient, -AB(PBA - P)/Q.A
CLL	Rolling-moment coefficient, rolling moment/Q.A.B
CLM	Total pitching-moment coefficient, pitching moment/Q.A. $\bar{c}$
CLN	Yawing-moment coefficient, yawing moment/Q.A.B
CN	Normal-force coefficient, normal force/Q.A
CP	Pressure coefficient
CY	Side-force coefficient, side force/Q.A
FS	Fuselage station, in.
M	Free-stream Mach number
P	Free-stream static pressure, psfa
PART	Run (data set) identification number
PBA	Average base pressure, psfa
PHIA	Model roll angle, deg

Accession For	
NTIS GRA&I	
DDC TAB	
Unannounced	
Justification	
By _____	
Distribution/	
Availability Codes	
Dist	Avail and/or special
A	

PT	Total pressure measured in the tunnel stilling chamber, psfa
PTi	Preston tube pressures, psfa (see Fig. 1c)
Q	Free-stream dynamic pressure, psf
WL	Model water line, in.
X/C	Fraction of wing chord measured from the leading edge
Y/C	Fraction of wing chord measured vertically from chord line
$\Lambda$	Wing leading-edge sweep, deg

## 1.0 INTRODUCTION

The work reported herein was conducted by the Arnold Engineering Development Center (AEDC), Arnold Air Force Station, Tennessee, under Program Element 65807F. The Air Force project monitor was Mr. A. F. Money. The objective of the Flight Vehicle Motion Simulation project (P32F-30) is to provide a motion analysis and simulation capability at the AEDC and to stay abreast of and contribute to technology in three areas: (1) dynamic derivative estimation, (2) airframe flexibility effects, and (3) aerodynamic hysteresis. The wind tunnel test, reported on herein, was conducted in support of the hysteresis phase of the project under ARO Project No. P41C-A3 in the Aerodynamic Wind Tunnel (4T) from March 27 through April 5, 1979.

The test objectives were to obtain (1) force and wing pressure data on a 1/20-scale model of the F-4C aircraft and (2) force data on a 1/24-scale model of the F-111 aircraft with wing sweep angles of 26 and 54 deg in regions of aerodynamic hysteresis. The test was conducted in three phases: (1) wing pressure data for the F-4C model (the model was non-metric during this phase), (2) force data for the F-4C model (pressure lines were disconnected near the wing trailing edge), and (3) force data for the F-111 model. In addition, tuft and oil flow visualization data were obtained for selected configurations.

Requests data from these tests should be addressed to the Director of Test Engineering (AEDC/DOT), Arnold Air Force Station, Tennessee 37389. A copy of the final data is on file on microfilm at AEDC.

## 2.0 APPARATUS

### 2.1 TEST FACILITY

The Aerodynamic Wind Tunnel (4T) is closed-loop continuous flow, variable-density tunnel in which the Mach number can be varied from 0.1 to 1.3 and can be set at discrete Mach numbers of 1.6 and 2.0 by placing nozzle inserts over the permanent sonic nozzle. At all Mach numbers, the stagnation pressure can be varied from 300 to 3,700, psfa. The test section is 4 ft square and 12.5 ft long with perforated variable-porosity (0.5- to 10-percent open) walls. It is completely enclosed in a plenum chamber from which the air

can be evacuated, allowing part of the tunnel airflow to be removed through the perforated walls of the test section. The model support system consists of a sector and sting attachment which has a pitch angle capability of -8 to 28 deg with respect to the tunnel centerline and a roll capability of -180 to 180 deg about the sting centerline. A more complete description of<sup>1</sup> the tunnel may be found in the Test Facilities Handbook.

## 2.2 TEST ARTICLES

Details of the 1/20-scale F-4C model are presented in Figure 1a. The left wing of the model was constructed with 74 static pressure orifices located at two spanwise stations as shown in Fig. 1b. Figure 1c presents an identification key as used in the tabulated wing pressure data. Tabulated locations of the wing static pressure orifices are given in Table 1. A Preston tube was located on the left wing upper surface as shown in Fig. 1c and detailed in Fig. 1d. Various simulated leading-edge slats which were tested with the basic wing are shown in Fig. 1e. A configuration identification free laminar-to-turbulent boundary layer transition was allowed on all model components.

Details of the 1/24-scale F-111 model are presented in Fig. 2a. For limited testing, the boundary layer was tripped by applying No. 150 glass beads as shown in Fig. 2b. Both aircraft models were tested without pylons or external stores. The models installed in the tunnel are shown in Fig. 3.

## 2.3 INSTRUMENTATION

A six-component, internal strain-gage balance was used to measure the aerodynamic forces and moments for each of the models tested; however, the force and moment data

---

<sup>1</sup>Test Facilities Handbook (Tenth Edition). "Propulsion Wind Tunnel Facility, Vol. 4." Arnold Engineering Development Center, May 1974

obtained during Phase 1 must be used with caution because the model was non-metric due to external wing pressure tubes. Base pressures, total pressure at the exit plane of the flow through ducts, and one cavity pressure for the F-111 model were measured using orifice tubes connected to differential pressure transducers of the PWT 4T pressure system. During Phase 1, the PWT 4T pressure system was used to measure the pressure sensed at the wing orifices of the F-4 model. A camera was installed in the top or side wall of the tunnel to provide flow visualization data.

Electrical signals from the balances, pressure transducers, and standard tunnel instrumentation were processed by the PWT data acquisition system for online data reduction. The balance outputs were also recorded on an oscilloscope for monitoring model-balance dynamics. Selected coefficients were also graphically displayed on a cathode ray tube plotter during the test for online evaluation of data.

### 3.0 TEST DESCRIPTION

#### 3.1 TEST CONDITIONS AND PROCEDURES

The nominal test conditions at which the test was conducted are listed in Table 3. Force and moment data were obtained while varying the model angle of attack or the sideslip angle at a constant Mach number and total stagnation pressure. All polars were run automatically (pitch-pause) utilizing online computer facilities which set the model pitch and roll angles to give the prescribed values of angle of attack and sideslip angle. Angle of attack was varied from -2 to 24 deg and angle of sideslip was varied from -12 to 12 deg. In addition to the force and moment data, selected configurations were examined using flow-visualization techniques. Fluorescent tufts were attached to the model or fluorescent oil was painted on the model surfaces, after which the test conditions were established and the model attitude was set. The model was then photographed using an ultraviolet flash. Two typical photographs obtained in this manner are presented in Fig. 4.

#### 3.2 CORRECTIONS

The angle of attack and sideslip angle were corrected for sting and balance deflections caused by aerodynamic loads. Corrections for the components of model weight, normally termed static tares, were also applied to the data. Several of the model configurations were tested both upright and inverted to provide the data to correct for the tunnel flow angularity in the pitch plane.

### 3.3 DATA REDUCTION

The model aerodynamic forces and moments were reduced to coefficient form in the body and stability-axes systems. The model base pressure was measured and used to determine the base axial-force which was then used to determine the forebody coefficients for the F-111 model only. Moment reference points for the F-4 and F-111 models are given in Fig. 1a and 2a, respectively.



### 3.4 UNCERTAINTY/PRECISION OF MEASUREMENTS

The data uncertainties determined for a 95-percent confidence level are presented in Table 4. The aerodynamic coefficient uncertainties include the uncertainties of the Mach number and dynamic pressure along with the uncertainty contribution associated with the particular balance, transducers, and data acquisition system.

The precision in setting and maintaining a specific Mach number was  $\pm 0.005$ . The Mach number variation in the test section occupied by the model was no greater than  $\pm 0.005$  for Mach numbers up to 0.95 and  $\pm 0.01$  for Mach numbers greater than 1.0. The uncertainty in the model angle of attack and roll angle was 0.1 deg and  $\pm 0.30$  deg, respectively.


## 4.0 DATA PACKAGE PRESENTATION

The final data package contained tabulated data, flow visualization photographs, and installation photographs. A part number summary of the data is presented in Table 5. A sample of the point-by-point test data for Phase I is shown in Table 6a. An example of the summary test data is shown in Table 6b. All data parameters used herein are defined in the nomenclature of this report. The nomenclature for the parameters appearing in the tabulated data is presented in Table 7.




a. General arrangement drawing

Figure 1. Details and Dimensions of the F-4C Model





b. Wing cross-section of pressure orifice locations

Figure 1. Continued




c. Identification of wing pressure orifices

Figure 1. Continued



d. Preston tube details


Figure 1. Continued




S1  
PLAN VIEW OF OUTER PANEL




TYPICAL CROSS SECTION



S2  
PLAN VIEW OF INNER PANEL




TYPICAL CROSS SECTION



S3  
PLAN VIEW OF INNER PANEL


BL in Inches



TYPICAL CROSS SECTION


e. Simulated leading-edge slats

Figure 1. Concluded



a. General arrangement drawing

Figure 2. Details and Dimensions of the F-111 Model




DIMENSIONS IN INCHES  
#150 GLASS BEADS

NOTE:

TRANSITION STRIP USED ONLY  
FOR LIMITED TESTING


b. Boundary layer transition strip location

Figure 2. Concluded



a. F-4C - Configuration 1  
Figure 3. Model Installation in Tunnel 4T

b. F-4C ~ Configuration 2  
Figure 3. Continued





c. F-111 - Configuration 7  
Figure 3. Concluded

a. Tuft Flow Visualization




Figure 4. Typical Flow Visualization Results;  $M = 0.9$ ,  
 $\alpha = 15$  deg,  $\beta = 2$  deg (Increasing  $\beta$ )

b. Oil-Flow  
Figure 4. Concluded




Table 1. Tabulated Locations of Wing Static Pressure Orifices

Inboard Upper Surface

NO.	X/C	Y/C	NO.	X/C	Y/C	NO.	X/C	Y/C
1	0	0	14	0.2998	0.03050	28	0.6610	0.02369
2	0.00997	0.00883	15	0.3199	0.03067	29	0.6822	0.02255
3	0.0255	0.01406	16	0.3509	0.03081	30	0.7013	0.02145
4	0.0501	0.01908	17	0.3811	0.03077	31	0.7204	0.02029
5	0.0755	0.02230	18	0.4104	0.03065	32	0.7410	0.01888
6	0.0999	0.02436	19	0.4405	0.02038	33	0.7613	0.01745
7	0.1291	0.02585	20	0.4708	0.02995	34	0.7810	0.01604
8	0.1611	0.02731	21	0.5007	0.02914	35	0.8006	0.01465
9	0.2004	0.02866	22	0.5308	0.02868	36	0.8259	0.01283
10	0.2212	0.02919	23	0.5611	0.02781	37	0.8514	0.01100
11	0.2409	0.02962	24	0.5812	0.02714	38	0.8760	0.00925
12	0.2606	0.02997	25	0.6019	0.02637	39	0.9010	0.00747
13	0.2801	0.03027	26	0.6204	0.02562	40	0.9506	0.00399
			27	0.6415	0.02465	41	1.0000	0.00042

Inboard Lower Surface

1	0	0	4	0.0986	0.01442	7	0.7035	0.01796
2	0.0232	0.00934	5	0.2995	0.02259	8	0.9013	0.00633
3	0.0528	0.01214	6	0.4983	0.02377	9	1.0000	0.00042

Outboard Upper Surface

1	0	0	8	0.2584	0.02294	15	0.6552	0.01825
2	0.0211	0.01016	9	0.3199	0.02350	16	0.7056	0.01621
3	0.0482	0.01432	10	0.3826	0.02356	17	0.7559	0.01377
4	0.0787	0.01684	11	0.4420	0.02308	18	0.8061	0.01092
5	0.1192	0.01888	12	0.5024	0.02235	19	0.8564	0.00695
6	0.1489	0.02022	13	0.5532	0.02132	20	0.9083	0.00569
7	0.2001	0.02178	14	0.6055	0.01992	21	1.0000	0.00085

Outboard Lower Surface

1	0	0	3	0.1055	0.00340	5	0.7056	0.00952
2	0.0627	0.00360	4	0.3525	0.00886	6	0.9083	0.00360
						7	1.0000	0.00085

Table 2. Model Configuration Nomenclature

<u>Configuration No.</u>	<u>Configuration</u>
1.	Baseline F-4C model
2.	F-4C with $S_1$ , $S_2$ , and $S_3$
3.	F-4C with $S_3$
4.	F-4C with $S_2$
5.	F-4C with $S_1$ and $S_2$
6.	F-4C with $S_1$
7.	F-111 with boundary layer transition strip, $\Lambda = 54$ deg
8.	F-111 clean, $\Lambda = 54$ deg
9.	F-111 clean, $\Lambda = 26$ deg

**Table 3. Summary of Nominal Test Conditions**

M	PT psfa	Q psf	R $\times 10^{-6}$ 1/ft
0.70	1200	295	2.18
0.80		352	2.32
0.85		378	2.37
0.90		402	2.42
0.95		424	2.51
1.10		476	2.50
1.20		500	2.52
1.30	↓	513	2.50

Table 4. Data Uncertainties

a. F-4 Model

M	$\pm \Delta CN$	$\pm \Delta CY$	$\pm \Delta CA$	$\pm \Delta CLM$	$\pm \Delta CLN$	$\pm \Delta CLL$	$\pm \Delta CP$
0.70	0.03	0.008	0.004	0.009	0.002	0.001	0.018 + 0.005 CP
0.80	0.02	0.007	0.003	0.007			0.015 + 0.004 CP
0.85		↓	↓	↓			0.013 + 0.003 CP
0.90		0.006		0.006	↓		0.012 + 0.003 CP
0.95	↓	↓	↓	↓	0.001	↓	↓

Table 4. Concluded

## b. F-111 Model

M	$\pm \Delta CN$	$\pm \Delta CY$	$\pm \Delta CA$	$\pm \Delta CLM$	$\pm \Delta CLN$	$\pm \Delta CLL$	$\pm \Delta CP$
0.70	0.02	0.005	0.003	0.007	0.001	0.001	$0.018 + 0.005$ CP
0.80	↓	0.004	↓	0.006			$0.015 + 0.004$ CP
0.90	0.01	0.003	0.002	0.005			$0.012 + 0.003$ CP
0.95				↓			↓
1.10				0.004			$0.010 + 0.002$ CP
1.20				↓			$0.009 + 0.002$ CP
1.30	↓	↓	↓	↓	↓	↓	↓

Table 5. Test Program Part Number Summary

PHASE	CONFIG	ALFA	BETA	PHIA	M			
					0 . 70	0 . 80	0 . 85	0 . 90
1	1	V	0	0 / 180	65 / 66	70 / 71	73 / 74	25 / 26
		V	↓	0	67 / 68	72	82	28
		5	V					92
		10						34
		15						35
	20			69	81 / 88		32 / 33	93
		15	↓					49
	2	V	0	0	108	106	98	105
	3	V	0	0	109	107	99	100
	4	V	0	0			114	
	6	V	0	0			115	
		15	V				122 <sup>2</sup>	
		15	V				1212	
		15	V				1262	
		15	V				127	
		↓						

V - Variable

1 - Time Dependence/Model Movement Studies

2 - Flow-Visualization

Table 5. Continued

PHASE	CONFIG	ALFA	BETA	PHIA	M				
					0.70	0.80	0.85	0.90	0.95
2	1	V	0	0	153	155	157	135	159
		5	V					137	
		10						138	
		15			154	156	158	136	160
		20						139	
		15						140 → 152 <sup>1</sup>	
								167 <sup>2</sup> /168 <sup>2</sup>	
								185 <sup>2</sup> /187 <sup>2</sup> /193 <sup>2</sup>	
		2	V	0	0			180	
			15	V				178 <sup>2</sup> /179 <sup>2</sup>	
			V						

V - Variable

1 - Time Dependence/Model Movement Studies

2 - Flow Visualization

Table 5. Concluded

PHASE	CONFIG	ALFA	BETA	PHIA	M						
					0 . 70	0 . 80	0 . 90	0 . 95	1 . 10	1 . 20	1 . 30
3	7	V	0	0					240	244	248
		↓	↓	180					239	245	249
		15	V	90					241	246	250
		↓	↓	-90					247	251	
	8	V	0	180	266			265	264	260	259
		15	V	90					263	262	257
		↓	↓	-90					261	258	
		↓	↓						270	2	
	9	V	0	0	275	277	278	282			
		↓	↓	180	274	276	279	283			
		15	V	90							
		↓	↓	-90			280	281			
		↓	↓						287	↔	289 <sup>2</sup>

V - Variable  
2 - Flow Visualization

DATE: 5-3-74 PROJECT NO. PA1C-A3C  
 ARO, INC.  
 AEDC DIVISION  
 AERODINAMICS CORPORATION COMPANY  
 PROPULSION WIND TUNNEL  
 ARNOLD AIR FORCE STATION, TENNESSEE

Table 6. Format for Tabulated Data

B. Phase 1 point-by-point

AERODYNAMIC HISTORICALS PHASE 1											
CONFIGURATION 1 SWEEP 51.0											
BODY AXIS (BALANCE BRIDGED)											
STABILITY AXIS (BALANCE BRIDGED)											
DATE	DAY	HR	MIN	SC	MD	SCHED MODE	ENCODE MODE	PHAS	DATE	WIND-OFF	AEDC PROPULSION WIND TUNNEL
50 7 PA1C-A3C TC639	3/29/74	08	14:42:4	:4	0:30:00	0:00:05	B	19	3 05-03-79	0.0/ 1	TRANSDUCIC 41
4 07 Q P R10-6 ALP1	P11	TTA-1	TTB-2	P1A-1	P1B-2	PCA-1	PCB-2	PF	TPM	WA	PCM SC100 PM TDP
0.932 1192.9 4322.4	709.2	2.434	10.36	-0.4	82.7	A3.0	1199.9	1200.5	716.8	942.3	1.273 0.00 0.99 0.139 1097. -1.6
BALANCE READINGS (BALANCE BRIDGED)											
ROLL - ROLL	ROLL	ROLL	PING	PING	MNG	FVG	MNG	FAG	MIG	PCAV	PCAV
-94.7	-79	415	-123	1059	-66	310.6	20.9	3.6	-26.2	21.8	-7.0
NET FORCES AND TRANSFERRED MOMENTS											
PN	WY	WY	WY	WY	WY	WY	WY	WY	WY	WY	WY
373.1	-421.7	9.6	-29.4	10.8	-6.3	-0.9	-59.4	-110.7	-3.4	-0.1	11.0
SLOPE E-JUST											
2.0	30	0	18	70	42	0	10.9	0	22	46	4.3
INBOARD-UPPER											
CP	X/C	CP	X/C	CP	X/C	CP	X/C	CP	X/C	CP	CP
CP1	0.3	-0.4686	CD22	0.530	-0.4571	CP62	0.025	0.0	CP49	0.3	0.4069
CP2	0.210	-0.5876	CP73	0.360	-0.3806	CP43	0.050	0.3221	CP50	0.020	0.050
CP3	0.325	-0.5074	CP24	0.580	-0.4820	CP45	0.100	0.2635	CP51	0.150	0.100
CP4	0.350	-1.0843	CP25	0.600	0.0	CP46	0.100	0.1780	CP52	0.350	0.0
CP5	0.375	-1.0319	CP26	0.620	-0.1975	CP40	0.500	-0.0054	CP53	0.120	-0.0028
CP6	0.100	0.3	CP27	0.640	-0.3888	CP47	0.700	0.0224	CP54	0.150	0.0
CP7	0.130	-0.2221	CP28	0.660	-0.3719	CP48	0.900	-0.9295	CP55	0.200	-0.6820
CP8	0.160	-0.4643	CP29	0.680	-0.1461	CP49	0.900	-0.9295	CP56	0.260	-0.6406
CP9	0.200	-0.2357	CP30	0.700	-0.3167	CP57	0.320	-0.6294	CP57	0.380	-0.5931
CP10	0.220	-0.2280	CP31	0.720	-0.2879	CP58	0.480	-0.5719	CP59	0.440	-0.5319
CP11	0.240	-0.2104	CP32	0.740	-0.1585	CP60	0.500	-0.5389	CP61	0.550	-0.4956
CP12	0.250	-0.2835	CP33	0.760	-0.2245	CP62	0.600	-0.4670	CP63	0.650	-0.4601
CP13	0.240	-0.4560	CP34	0.780	0.0	CP64	0.700	-0.4601	CP65	0.750	-0.3948
CP14	0.330	0.0	CP35	0.800	-0.2072	CP66	0.800	-0.4129	CP67	0.850	-0.2675
CP15	0.320	-0.2016	CP36	0.825	-0.1599	CP68	0.900	-0.3736	CP69	1.000	0.0
CP16	0.150	-0.7337	CP37	0.850	-0.2649	CP70	0.950	-0.4670	CP71	1.000	-0.4601
CP17	0.380	-0.6785	CP38	0.875	-0.1597	CP72	0.700	-0.3948	CP73	0.750	-0.3948
CP18	0.410	-0.6524	CP39	0.900	-0.1316	CP74	0.900	-0.1291	CP75	0.950	-0.1291
CP19	0.440	-0.2899	CP40	0.950	-0.1056	CP76	0.950	-0.1056	CP77	1.000	-0.1056
CP20	0.370	-0.5983	CP41	1.000	0.0523	CP78	0.950	-0.3736	CP79	1.000	0.0
TUNNEL CONDITIONS											
PT1	PT2	PT3	RETAN	PC BL1	PC BL2	PTBL1	PTBL2	PTBL3	PTBL4	PTBL5	PTBL6
521.1	959.9	982.7	16.21	712.1	713.0	1197.2	1198.9				

DATE: 4-29-74 PROJECT NO. 4113-A-3  
 AEDC INC.  
 AERODYNAMIC COMPUTATION COMPANY  
 PROPOSITION WIND TUNNEL  
 ARMY AIR FORCE STATION, TENNESSEE

Table 6. Continued

b. Summary data

POINT	PROJECT	TEST	DATE	DAY	HR	MIN	SC	WIND	SCODE	MODE	EBCODE	WIND-OFF AEDC PROPULSION WIND TUNNEL						
								95	101.135	1.100	0.005	12	4-20-74	237/3	TRANSONIC ST			
1	91	0	MALEB	AEDC	PHL	11A-1	11B-2	P1A-1	P1B-2	PCA-1	PCB-2	PF	TPH	MA	PPB	SCALAR	PM	IDP
1-299	1292-4	513.5	413.8	2.995	0.31	90.0	101.8	109.8	1202.7	446.0	445.5	801.8	1.697	0.00	6.22	0.110	1031.	-7.2

AERODYNAMIC MEASUREMENTS PHASE 3  
 CONFIGURATION 7 SWEEP 56.0

Summary 1. DYNAMIC

POINT	ALFA	BETA	PHI	EN	CF	CA	CLL	CLM	CLN	CAF	CPL	CPL2	CPL3	CPCAV
5	16.30	0.15	90.0	1.100	-0.0056	0.0346	-0.0119	-0.5154	-0.0024	0.0274	-0.2874	-0.2412	0.0	-0.1032
A	16.20	-21.92	90.0	0.0963	-0.0213	0.0392	-0.0016	-0.5699	-0.0008	0.0295	-0.2854	-0.2150	0.0	-0.1044
11	16.31	-31.90	90.1	1.0734	-0.0561	0.0454	-0.0040	-0.5638	-0.0018	0.0355	-0.2979	-0.2133	0.0	-0.1049
11	16.31	-55.41	40.0	1.0374	-0.0902	0.0662	-0.0108	-0.5557	-0.0031	0.0357	-0.3027	-0.2133	0.0	-0.1119
15	16.31	-71.94	90.0	0.0717	-0.1265	0.0717	-0.0172	-0.5472	-0.0013	0.0372	-0.3176	-0.2177	0.0	-0.1191
17	16.32	-66.42	89.9	1.0356	-0.0843	0.0442	-0.0119	-0.5539	-0.0003	0.0381	-0.3093	-0.2117	0.0	-0.1139
18	16.99	-24.95	90.0	1.0304	-0.0253	0.0425	-0.0067	-0.5609	0.0017	0.0325	-0.3022	-0.2689	0.0	-0.1040
19	16.39	-31.99	89.9	1.0503	-0.0165	0.0405	-0.0020	-0.5675	0.0028	0.0307	-0.2938	-0.2129	0.0	-0.1067
21	16.49	-0.00	-46.9	1.0442	-0.0275	0.0443	-0.0011	-0.5647	0.0053	0.0345	-0.2991	-0.2176	0.0	-0.1024
24	16.32	-22.01	89.9	1.0441	-0.0591	0.0320	-0.0084	-0.5703	0.0044	0.0222	-0.2837	-0.2186	0.0	-0.0917
24	16.49	-22.01	90.0	1.0405	-0.0408	0.0314	-0.0042	-0.5692	0.0045	0.0219	-0.2774	-0.2161	0.0	-0.1040
25	16.49	-6.01	90.0	1.0615	-0.1268	0.0383	-0.0119	-0.5681	0.0015	0.0283	-0.2795	-0.2280	0.0	-0.1167
25	16.41	4.03	90.0	1.0730	-0.1547	0.0400	-0.0202	-0.5574	0.0042	0.0248	-0.2648	-0.2603	0.0	-0.1205
26	16.91	9.38	-31.9	1.1561	-0.1925	0.0465	-0.0258	-0.5554	0.0056	0.0361	-0.2849	-0.3139	0.0	-0.1239
27	16.37	4.01	90.1	1.0726	-0.1172	0.0311	-0.0206	-0.5556	0.0029	0.0309	-0.2800	-0.3102	0.0	-0.1234
28	16.49	-6.08	40.1	1.0615	-0.1268	0.0383	-0.0149	-0.5605	-0.0008	0.0308	-0.2808	-0.2775	0.0	-0.1113
29	16.49	-6.05	90.1	1.0405	-0.0408	0.0364	-0.0100	-0.5656	-0.0015	0.0261	-0.2767	-0.2494	0.0	-0.1118
30	16.49	-2.03	90.0	1.0946	-0.0361	0.0360	-0.0050	-0.5690	-0.0022	0.0281	-0.2781	-0.2694	0.0	-0.1017
31	16.49	0.04	90.0	1.0405	-0.0087	0.0317	-0.0017	-0.5687	-0.0022	0.0319	-0.2844	-0.2944	0.0	-0.1046
32	16.99	31.98	90.1	1.0538	-0.0217	0.0441	-0.0016	-0.5569	-0.0007	0.0332	-0.2958	-0.2195	0.0	-0.1021
33	16.92	-21.91	90.2	1.0916	-0.0537	0.0459	-0.0060	-0.5592	-0.0012	0.0360	-0.2964	-0.2570	0.0	-0.1012
34	16.91	-25.69	90.2	1.0562	-0.0388	0.0385	-0.0111	-0.5526	-0.0022	0.0385	-0.2926	-0.2222	0.0	-0.0998
35	16.92	-27.92	90.1	1.0404	0.1263	0.0504	0.0171	-0.5562	-0.0035	0.0402	-0.3127	-0.2740	0.0	-0.1180

DATE: 20-7-74 PROJECT NO. 2417-A30

ARO, L.G.  
AEUC DIVISION  
A STENDUP CORPORATION COMPANY  
PROPELLSION & IN TUNNEL  
ARNOLD AIR FORCE STATION, TENNESSEE

Table 6. Concluded

b. Concluded

POINT	TEST	DATE	DAY	HR	MIN	SEC	DM	SCHED MODE	ENCODE PROPS DATE	WIND-OFF	AEDC PROPSINN WIND TUNNEL
5	5 2417-A30	10/6/69	9/	5/74	95	10147135	1.300	0.005	H 19 0 04-20-74	237/-3	TRANSONIC AT
6											
7											
8											
9											
10											
11											
12											
13											
14											
15											
16											
17											
18											
19											
20											
21											
22											
23											
24											
25											
26											
27											
28											
29											
30											
31											
32											
33											
34											
35											

AERODYNAMIC MYSTESIS PHASE 3  
CONFIGURATION 7 SLEEP SA.0

Summary 2. Stability Axis

POINT	WHTA	W-1A	CL	CY	COS	CLLW	CLM	CLNw	COF	COI	CPI	CPE
5	16.90	0.015	20.0	1.0539	-0.0056	0.3203	-0.0028	-0.5754	-0.0018	0.3107	0.0096	1.2700
6	16.90	-1.042	10.0	1.0494	-0.0013	0.3213	-0.0012	-0.5690	-0.0012	0.3103	0.0094	1.2926
7	16.90	-1.040	10.0	1.0494	-0.0013	0.3194	-0.0013	-0.5634	-0.0013	0.3145	0.0095	1.3179
8	16.90	-1.040	10.0	1.0494	-0.0013	0.3251	-0.0053	-0.5634	-0.0013	0.3179	1.2161	
9	16.90	-1.040	10.0	1.0494	-0.0013	0.3251	-0.0053	-0.5634	-0.0013	0.3179	1.2161	
10	16.90	-1.040	10.0	1.0494	-0.0013	0.3251	-0.0053	-0.5634	-0.0013	0.3179	1.2161	
11	16.90	-1.040	10.0	1.0494	-0.0013	0.3251	-0.0053	-0.5634	-0.0013	0.3179	1.2161	
12	16.90	-1.040	10.0	1.0494	-0.0013	0.3251	-0.0053	-0.5634	-0.0013	0.3179	1.2161	
13	16.91	-5.461	30.0	1.02367	0.02042	0.3249	-0.0097	-0.5557	-0.0058	0.3152	0.02032	1.2292
14	16.91	-7.95	40.0	1.0321	0.01285	0.3242	-0.0184	-0.5472	-0.0077	0.3142	0.0099	1.3445
15	16.91	-7.95	40.0	1.0321	0.01285	0.3242	-0.0184	-0.5472	-0.0077	0.3142	0.0099	1.3445
16	16.91	-7.95	40.0	1.0321	0.01285	0.3242	-0.0184	-0.5472	-0.0077	0.3142	0.0099	1.3445
17	16.91	-6.02	34.9	1.0374	0.00943	0.3217	0.0114	-0.5539	-0.0038	0.3119	0.0095	1.3293
18	16.91	-6.05	30.0	1.0324	0.01453	0.3214	0.0110	-0.5604	-0.0011	0.3118	0.0096	1.3160
19	16.91	-1.040	10.0	1.0494	-0.0013	0.3216	-0.0070	-0.5675	-0.0014	0.3111	0.0095	1.2937
20	16.91	-1.040	10.0	1.0494	-0.0013	0.3206	-0.0026	-0.5675	-0.0014	0.3111	0.0095	1.2937
21	16.91	-1.040	10.0	1.0494	-0.0013	0.3206	-0.0026	-0.5675	-0.0014	0.3111	0.0095	1.2937
22	16.91	-2.01	37.9	1.04592	-0.04594	0.3121	-0.0231	-0.5703	-0.0054	0.3027	0.0095	1.3222
23	16.91	4.00	40.0	1.0354	-0.0096	0.3110	-0.0077	-0.5641	-0.0077	0.3015	0.0095	1.2162
24	16.91	6.01	34.9	1.0355	-0.01284	0.3110	-0.0119	-0.5624	-0.0100	0.3053	0.0097	1.3010
25	16.91	8.03	44.9	1.0365	-0.01265	0.3147	-0.0170	-0.5574	-0.0111	0.3049	0.0098	0.9616
26	16.91	9.04	44.9	1.03192	-0.01925	0.3193	-0.0232	-0.5541	-0.0128	0.3093	0.0101	0.8245
27	16.91	9.01	40.1	1.0263	-0.0172	0.3150	-0.0192	-0.5568	-0.0091	0.3051	0.0094	0.8662
28	16.91	8.00	30.1	1.03183	-0.01086	0.3173	-0.0162	-0.5605	-0.0046	0.3075	0.0095	1.3612
29	16.91	4.01	40.1	1.0354	-0.00450	0.3154	-0.0101	-0.5656	-0.0012	0.3058	0.0097	1.3151
30	16.91	2.09	34.9	1.0352	-0.00482	0.3161	-0.0054	-0.5690	-0.0088	0.3045	0.0095	1.2853
31	16.90	0.04	46.0	1.03685	-0.00947	0.3221	-0.0022	-0.5617	-0.0017	0.3126	0.0095	1.3212
32	16.90	-1.040	90.1	1.03657	-0.0217	0.3239	-0.0014	-0.5649	-0.0011	0.3144	0.0095	1.2730
33	16.92	-3.01	90.2	1.05432	0.00537	0.3254	0.0055	-0.5592	-0.0027	0.3158	0.0095	1.3159
34	16.91	-5.008	36.1	1.03112	0.00884	0.3266	0.0002	-0.5628	-0.0050	0.3161	0.0095	1.2288
35	16.92	-7.02	40.1	1.03116	0.01263	0.3270	0.0156	-0.5467	-0.0078	0.3171	0.0099	1.3352

DATE: 20-7-74 PROJECT NO. 2417-A30

ARO, L.G.  
AEUC DIVISION  
A STENDUP CORPORATION COMPANY  
PROPELLSION & IN TUNNEL  
ARNOLD AIR FORCE STATION, TENNESSEE

DATE: 20-7-74 PROJECT NO. 2417-A30

ARO, L.G.  
AEUC DIVISION  
A STENDUP CORPORATION COMPANY  
PROPELLSION & IN TUNNEL  
ARNOLD AIR FORCE STATION, TENNESSEE

Table 7. Tabulated Data Nomenclature

Test Data Identification and Wind Tunnel Parameters

PART	Run (data set) identification number
POINT	Data point number
PROJECT	Project number
TEST	Test number
DATE	Date of data acquisition
DAY	Day (of year) of data acquisition
HR	Hour of data acquisition
MN	Minute of data acquisition
SC	Second of data acquisition
MB	Set point Mach number
DM	Mach number tolerance
SCHED	Tunnel wall porosity schedule
MODE	Data acquisition mode
ERCODE	Error code
PROS DATE	Date of data processing
WIND OFF	Wind-off part and point number
M	Free-stream Mach number
PT	Free-stream stagnation pressure, psfa
Q	Free-stream dynamic pressure, psf
P	Free-stream static pressure, psfa
RX10-6	Free-stream unit Reynolds number $\times 10^{-6}$ , $10^6/\text{ft}$
ALFI	Pitch sector indicated pitch angle, deg
PHII	Pitch sector indicated roll angle, deg
TTA-X	Total temperature measured in the tunnel stilling chamber - A system, °F
TTB-X	Total temperature measured in the tunnel stilling chamber - B system, °F

Table 7. Continued

PTA-X	Total pressure measured in the tunnel stilling chamber - A system, psfa
PTB-X	Total pressure measured in the tunnel stilling chamber - B system, psfa
PCA-X	Tunnel plenum chamber pressure - A system, psfa
PCB-X	Tunnel plenum chamber pressure - B system, psfa
PE	Tunnel diffuser pressure, psfa
TPR	Tunnel pressure ratio, PT/PE
WA	Test section wall angle, deg
POR	Average tunnel wall porosity , percent of wall area open to test section plenum
SCX100	Tunnel specific humidity $\times 100$ , lb/lb $\times 10^{-2}$
PM	Hygrometer mixture pressure, psfa
TDP	Hygrometer dew point temperature, °F

Note: The suffixed "X's" with TT, PT, and PC indicate the primary system and the program checks on system agreement. The suffixed nomenclature is as follows:

- X = 1 Primary system
- X = 2 Secondary system
- X = 0 Delete checks on system agreement

#### Body Axes Coefficients/Base Pressures/Exit Pressures

ALFA	Model angle of attack measured between the relative wind vector and the reference water line, deg
BETA	Model sideslip angle, deg
PHIA	Model roll angle, positive right wing down, deg
CN	Normal-force coefficient
CLM	Pitching-moment coefficient
CY	Side-force coefficient
CLN	Yawing-moment coefficient

Table 7. Continued

CLL	Rolling-moment coefficient
CA	Total axial-force coefficient
CAF	Forebody axial-force coefficient, CA-CAB
CPB <sub>i</sub>	Base pressure coefficient
CPE <sub>i</sub>	Flow-thru duct total exit pressure coefficients
<u>Stability Axes</u>	
CLS	Lift coefficient
CLM	Pitching-moment coefficient
CY	Side-force coefficient
CLNW	Yawing-moment coefficient
CLLS	Rolling-moment coefficient
CD	Total drag coefficient
CDB	Base drag coefficient
CDF	Forebody drag coefficient, CD-CDB
PB <sub>i</sub>	Base pressure, psfa
PE <sub>i</sub>	Flow thru duct total exit pressure, psfa
<u>Balance Readings/Gross Forces</u>	
RMM1	Balance forward pitching moment gage reading
RMN1	Balance forward yawing moment reading
RFA	Balance axial force gage reading
RML	Balance rolling moment gage reading
RMM2	Balance aft pitching moment gage reading
RMN2	Balance aft yawing moment gage reading
FNG	Gross normal force, lb
MMG	Gross pitching moment, in.-lb
FYG	Gross side force, lb

Table 7. Continued

MNG	Gross yawing moment, in.-lb
FAG	Gross axial force, lb
MLG	Gross rolling moment, in.-lb
PCAV	Cavity pressure, psfa

Net Forces and Transferred Moments/Static Tares

FN	Net normal force, lb
MM	Net transferred pitching moment, in.-lb
FY	Net side force, lb
MN	Net transferred yawing moment, in.-lb
FA	Net total axial force, lb
ML	Net rolling moment, in.-lb
ALFO	Flow correction angle in pitch, deg
FNST	Normal force tare, lb
MMST	Pitching moment tare, in.-lb
FYST	Side force tare, lb
MNST	Yawing moment tare, in.-lb
FAST	Axial force tare, lb
MLST	Rolling moment tare, in.-lb

4T Pressure System Information

SLOPE	Pressure settling slope criteria, psf/sec
T-OUT	Time out criteria, sec
FLAGi	Indicator if pressure settling criteria was settled at time of data acquisition (i = 1, loop 1; i = 2, loop 2)
TREQi	Time required for settling
LCSI	Last channel to settle
NLCSI	Next to last channel to settle

Table 7. Concluded

NCNSi	Number of channels not settled at time of data acquisition
<u>Phase 1 Pressures - Wing/Preston Tube/Tunnel Conditions</u>	
X/C	Fraction of wing chord measured from the leading edge
CPi	Wing pressure coefficient
PTi	Preston tube pressures, psfa
BETAM	Measured local wing surface flow angle in the yaw plane (Preston tube), deg
PCBLi	Tunnel plenum chamber pressure during data cycle - B system, psfa
PTBLi	Total pressure measured in the tunnel stilling chamber during data cycle - B system, psfa